
BARRIO HISTORICO

HISTORIC ZONE ADVISORY BOARD

HO-3, HPZ - 141-147 W. Simpson adobe rowhouses


T20CM06162, NOVEMBER 9, 2020







1 HZP AERIAL IMAGE (WITH DEVELOPMENT ZONE DOTTED IN RED, AS PER 5.8)
NOT TO SCALE



ARIZONA STATE HISTORIC PROPERTY INVENTORY

AKIZONA SIAI	E LIBIORIC L	KUPER
PROPERTY NAME		S-23, NF
LOCATION 141-147 West Simpson Str	reet	
CITY/TOWN/VICINITY Tucson	COUNTY Pima	
OWNER Rollings Motor Company		
901 E. Broadway Tucson, Az. 85719 FORM COMPLETED BY		
Tim Fisher, Dale Frens,	Janet Stewart	1//
DIA CONTRACTOR		1
PHOTO BY	DATE	7
Tim Fisher	July 1977	
VIEW Looking NE	3411	///
PRESENT USE Multi-family dwelling	ACREAGE	14/



PHYSICAL DESCRIPTION

Pre-1886

STYLE OR CULTURAL PERIOD
Transformed Sonoran
SIGNIFICANT DATES


Single story row houses with front facade built on property line; stuccoed adobe construction; hipped metal roof built over former parapet walls, gable dormer at center of street facade.

STATEMENT OF SIGNIFICANCE


Very good example of Transformed Sonoran row houses. This group is among the most noble structures in the district.

VERBAL BOUNDARY DESCRIPTION

Tueson Lot 6 Block 234. (This tax lot also includes 135-139 West Simpson)














EXISTING DOORS AND WINDOWS


















LEVEL 1 - DEMO SCALE: 1/8" = 1'-0"






SITE NEW WORK PLAN SCALE: 1/8" = 1'-0"







2 EAST ELEVATION



SOUTH - HISTORIC
SCALE: 1/8" = 1'-0"





NORTH - HISTORIC SCALE: 1/8" = 1'-0"

SUMMARY OF HISTORIC TREATMENTS

- 1. Exterior treatment is preservation.
- 2. Interior treatment is <u>rehabilitation</u>
- 3. Rising damp damage on south will be repaired. New plaster to match existing. New finish coat over all to match existing finish (sponge float).
- 4. South elevation: 2 x 6 wood door frames rebuilt with fixed-glass transoms. New doors (6 panel) wood or steel. <u>Please advise</u>.
- 5. South elevation: New double-hung windows wood or vinyl covered wood. <u>Please advise.</u>
- 6. Severely damaged 1950's south public sidewalk/driveway to be rebuilt. Foundation drain with brick cap added at base of adobe wall.
- 7. Main roof framing in need of structural repair (from interior).
- 8. North lean-to roof needs structural repair. Later addition north wall to be repaired (settled, out of plumb). New doors (6 panel) wood or steel. Please advise. 6 new double-hung windows wood or vinyl covered wood. Please advise. 3 windows filled-in and marked with score joint.
- 9. We respectfully request, Design Review Board decision with recommendations today, so that we can move forward on schedule.

Thank you.

Comments?
Questions?